BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/01/2015-16 Dated: 04-01-2016

APPROVED TENDER SCHEDULE –'B'

Item No: 28

Name of Work:-Construction of RCC drain at chowde swhari layout 6th cross roads in ward No- 02 of yelahanka Sub division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri T C PRATHAP	
				Rate	Rate in Words
1	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification,	Cum	208.50	183.00	Rupees one hundred eighty three only
2	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M	Cum	208.50	81.00	Rupees eighty one only
3	KSRRB M300-53: construction of embankment with approved material gravel/murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement table 300-2 complete as per specifications. (which includes cost of gravel/murrum, watering charges & compaction by vibratory roller) MORTH specification	Cum	52.50	295.00	Rupees two hundred ninety five only
4	KSRB-4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement at 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.465cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No.	Cum	56.21	4975.00	Rupees four thousand nine hundred seventy five only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri T C PRATHAP	
				Rate	Rate in Words
5	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications Specification,	Cum	66.77	5888.00	Rupees five thousand eight hundred eighty eight only
6	KSRB 4.9.2 providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	Qt	42.11	6632.00	Rupees six thousand six hundred thirty two only
7	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters, bttresses,buttresses plinth and string course including cost of all materials, labour complete as per specifications	Sqm	507.76	291.00	Rupees two hundred ninety one only
8	RCC Precast covering slab for drain (10cm thick)	Sqm	131.25	1423.00	Rupees one thousand four hundred twenty three only
9	KSRRB M600-6: cement concrete pavement, construction unreinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with 43 grade cement or any other type as per clause 1051.2.2 with 25mm and down size graded granite metal coarse aggregates and fine aggregtes with superplatisiser @ 3lts confirjming to IS103-1999 fine reaffirmed-2008 mixed in a concrete mixed of not cless than 0.6 cum capacity and appropriate weigh batcher as per approved mix design capacitylaid in approved fixed side form wedges stee plates including levellingthe from work as per deawing) & spreading the concrot and finished racer compacted using needle , screed and plate vibrator and finished in a continous operation including provision orf contraction , expansion construction and longitudinal joints including groove cutting charges joint filler separation memberane selant primer joint sealant admixdures ad approved curing compound finishing to lines and grades as per drwng complete as per specifin M 30 at 360 kg per cim coarse aggregate @ 0.69cum and fine aggregate @0.49cum	Cum	21.00	5659.00	Rupees five thousand six hundred fifty nine only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri T C PRATHAP	
				Rate	Rate in Words
10	Vaccum De- writing with vaccum pump and suction mat and compaction with skin flater clubbed with floatiog disc including cost of generator, HOM of machinery Sereed Vibratory Power Floaterblade and diisc etc. with all lead and lift. Page No 174 Item No 22.7 SR 2015-16	Sqm	210.00	92.00	Rupees ninety two only
11	Providing groove cutting for width of 5mm to 100m depth 80mm-100 including cost of cutting machine, generatoe & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot birumen fillars, and filler metal etc., including cost of conveyance of all materials,. Labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. do- for concrete pavement Item no 22.8.1 Page No 178 SR 2015-16	Rmt	72.00	118.00	Rupees one hundred eighteen only

T.C. Prathap
Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.